

DESCRIPTION

Insulated FRP Telescopic Earth/Discharge Rods manufactured in fully automatic Pultrusion Plant, having strong Electrical & Mechanical Strength.

Available Models:

- 11-33kV
- 33-66kV
- 66-132kV
- 132-220kV
- 400kV

SPECIFICATIONS

Material : FRP Pultruded

Process : Automatic Pultrusion Plant

Surface : Smooth and Glossy

Design : Telescopic

Locking : Push Button type Locking System

Total Sections : 03

Assembled Length : 15 feet

H.V.Test : 110 KV

Glass Content : 65 %.

Top Section Dia : 25 mm.

Bottom Section Dia : 45 mm.

Earthing : Die cast Aluminium Earthing instrument for
30mm Dia

Cable : 6 sq. mm. Copper cable 6 mts.

Clamp : Crocodile grounding clamp



*Technical Specifications & Appearance are subject to change without prior notice